



Rigola prefabricata
(sau monolita)
scara 1:50



Rigola prefabricata
(sau monolita)
scara 1:25




EXTRAS DE ARMATURA PLASA SUDATA
IN SANT RANFORSAT

TIP PLASA	ARIE (mp)
8X100X100	2060.80


Domenii de aplicare VOTS




STANGA		DREAPTA	
Km	Km	Km	Km
5+082	5+310	5+082	5+310
5+550	5+758	5+550	5+758
17+840	18+060	17+840	18+060
18+300	18+540	18+300	18+540



Caracteristicile betoanelor utilizate pentru
dispozitive de scurgere ape:
Referinta la normativul NE 012-1:2007/standardul SR EN 206-1

- Clasa de rezistenta la compresiune	C30/37
- Clasele de expunere (min)	XF4
- Dozaj minim de ciment (min)	340 kg/mc
- Tip ciment conf. SR EN 197-1:2002	CEM I: SRI; I-A 52.5, 42.5; CEM II: A/B-S, HIIA-S, A-LL;
- Raport apa/ciment (max)	0.5



<div>INVESTITOR</div> <div></div> <div>COMPANIA NATIONALA DE ADMINISTRARE A INFRASTRUCTURII RUTIERE S.A.</div>	<div>PROIECTANT GENERAL</div> <div></div> <div>D P CONSULT S.A.</div>	<div>AMPLASAMENT</div> <div></div>	<div>DENUMIRE PROIECT</div> <div>PROIECTARE SI EXECUTIE "VARIANTA DE OCOLIRE TIMISOARA SUD" ELABORARE PROIECT TEHNIC REST DE EXECUTAT</div>	<div>FAZA PROIECT</div> <div>PROIECT TEHNIC REST DE EXECUTAT</div>		<div>Manager de Proiect</div> <div>ing. Silvan Moldovan</div>		<div>REVIZII</div>			<div>DENUMIRE PLANSA</div> <div>DETALIU SANT TIP 7</div>
					<div>NR. REV.</div>	<div>DATA</div>		<div>SEMN.</div>			
			<div>NUMAR CONTRACT: 550/36/09.02.2023</div>	<div>Data : 03.2023</div>		<div>Sef Echipa Proiectare</div> <div>ing. Raul Cocis</div>					
			<div>NUMAR PROIECT : 556</div>	<div>VERIFICATOR TEHNIC</div>		<div>Inginer Proiectant Poduri</div> <div>ing. Attila Takacs</div>				<div>Scara : 1:50/1:25</div>	
						<div>Inginer Proiectant Drumuri</div> <div>ing. Valentin Oaida</div>				<div>NUMAR PLANSA</div> <div>556-VOTM-DET-12</div>	